



CONTRACT AWARD INFORMATION – WORKS

**BALLAST BAY SLIDE - SLOPE STABILIZATION AND ROAD REHABILITATION
PROJECT, TORTOLA, BVI**

1. **Bid Prices:**

Names of Bidders Submitting Bids	Country of Bidder	Bids Prices at Bid Opening (US\$)	Corrected Bid Prices (currency)
Caribbean Environmental Restoration Company Ltd	British Virgin Islands	1,009,583.85	985,409.15
Quality Construction Ltd	British Virgin Islands	1,064,148.38	1,107,078.20
Metro Construction Ltd	British Virgin Islands	1,147,934.79	1,147,934.79
JV: STO Enterprise/Autland Heavy Equipment Ltd	British Virgin Islands	1,087,582.43	1,054,125.93
Rufred Forbes & Associates Ltd	British Virgin Islands	1,208,458.90	1,272,005.24
D& B Heavy Equipment Services Ltd	British Virgin Islands	1,088,647.78	1,048,070.54
Tandem Development Ltd	British Virgin Islands	1,060,773.07	1,022,133.05

2. **Number of Bids Rejected:** 0

3. **Winning Bidder:** Joint Venture: STO Enterprise/Autland Heavy Equipment Ltd

4. **Final Awarded Price:** US\$1,054,125.93

5. **Commencement Date of Contract:** 19th October 2020

6. **Duration of Contract:** Eight (8) months

7. **Summary Scope of Contract:**

The works include, but are not limited to the following:

- General site clearance and disposal

Any bidder who wishes to ascertain the grounds on which its bid was not selected, should request an explanation from the Recipient of CDB Financing.

Telephone: (284) 393-8003 E-mail: feedback@bvirecovery.vg Website: www.bvirecovery.vg
First Floor, Ritter House, Wickham's Cay II, Tortola, VG 1110, Virgin Islands

- Demolition of existing sections of asphalt and reinforced concrete pavement
- Demolition of existing reinforced concrete box culvert
- Demolition of existing reinforced concrete retaining wall
- Construction of 120m of reinforced concrete pavement
- i. The road carriageway will be a constant 6.0m road width
- ii. Placing and compaction of 200mm thick Subbase to the proposed road alignment to 95% compaction modified proctor.
- iii. Placing of 120m of 150mm thick concrete with 50mm thick asphalt overlay
- Construction of 24m long by 5m high reinforced concrete retaining wall
- Construction of 10m reinforced concrete bridge slab and box culvert
- Construction of 30m long reinforced concrete wing walls to box culvert
- Construction of 80m of reinforced box drains with metal gratings
- Construction of 40m of river training works, trapezoidal stone pitching and berms to existing ghut
- Construction of 70m of raised reinforced concrete sidewalk

Note: Procurement Method: National Competitive Bidding (NCB)