



CONTRACT AWARD INFORMATION – WORKS

**GREAT MOUNTAIN SITE 2 - SLOPE STABILIZATION AND ROAD REHABILITATION
PROJECT, TORTOLA, BVI**

1. **Bid Prices:**

Names of Bidders Submitting Bids	Country of Bidder	Bids Prices at Bid Opening (US\$)	Corrected Bid Prices (currency)
Autland Heavy Equipment Ltd Co. Ltd	British Virgin Islands	447, 461.30	Nil
Caribbean Environmental Restoration Ltd	British Virgin Islands	605, 370.70	Nil
James Todman Construction	British Virgin Islands	640, 552.22	Nil
Quality Construction Ltd	British Virgin Islands	573, 649.71	Nil

2. **Number of Bids Rejected:** 0

3. **Winning Bidder:** Autland Heavy Equipment Co Ltd

4. **Final Awarded Price:** US\$447,461.30

5. **Commencement Date of Contract:** 19th October 2020

6. **Duration of Contract:** Four (4) months

7. **Summary Scope of Contract:**

The works include, but are not limited to the following:

- General site clearance and disposal
- Demolition of existing section asphalt and reinforced concrete pavement
- Demolition of existing reinforced concrete box culvert
- Road Carriageway

Any bidder who wishes to ascertain the grounds on which its bid was not selected, should request an explanation from the Recipient of CDB Financing.

Telephone: (284) 393-8003 E-mail: feedback@bvirecovery.vg Website: www.bvirecovery.vg
First Floor, Ritter House, Wickham's Cay II, Tortola, VG 1110, Virgin Islands

- i. The road carriageway will be a constant 6.0m road width
- ii. Placing and compaction of 200mm thick Subbase to the proposed road alignment to 95% compaction modified proctor.
- iii. Placing of 120m of 150mm thick concrete with 50mm thick asphalt overlay
 - Construction of 50m long by 2.7m high reinforced concrete retaining wall
 - Construction of reinforced concrete bridge slab and box culvert
 - Construction of 190m of reinforced kerb and slipper drains
 - Construction of 25m of river training works and trapezoidal stone pitching to existing ghut
 - Installation of 60m of guard rails

Note: Procurement Method: National Competitive Bidding (NCB)